



ROAD DEPARTMENT

## ADDENDUM NO. 1

### NE NEGUS WAY & NE 17TH ST. IMPROVEMENT

The Bidding Documents for the NE NEGUS WAY & NE 17TH ST. IMPROVEMENT project are amended as follows:

#### **SPECIAL PROVISIONS**

**Replace Section 00650.47 of the Special Provision with the following:**

**00650.47 Curing** – After completion of the final compaction and grading of the FDR base, seal the surface for curing with CSS-1 asphalt cement at a uniform application rate of 0.20-0.25 gallons per square yard to create a sealing membrane. Apply the CSS-1 as soon as possible, but not later than 24 hours after mixing the reclaimed material with cement slurry. The FDR base surface shall be free of all loose and extraneous materials and contain sufficient moisture to prevent excessive penetration of the asphalt cement prior to applying the CSS-1. FDR base curing seal coat work shall also comply with the requirements of Section 00730.

Apply sand cover immediately after application of the asphalt cement sufficient to prevent pickup of the sealant by vehicles and equipment. Sand shall be crushed or uncrushed Rock free of Clay, loam or other harmful substances and suitable for the purpose intended.

Allow finished FDR base to cure for a minimum of 36 hours before proof roll and paving.

\*\*\*

The Bidding Documents for the NE NEGUS WAY & NE 17TH ST. IMPROVEMENT project are amended as described above.

A handwritten signature in blue ink, appearing to read "Cody Smith".

Cody Smith, PE  
County Engineer

May 21, 2021

Date

I acknowledge receipt of Addendum Number 1.

\_\_\_\_\_  
SIGNATURE OF BIDDER

\_\_\_\_\_  
Date

**THIS ADDENDUM, EXCLUDING ATTACHMENTS, SHALL BE SIGNED AND SUBMITTED WITH THE BID PROPOSAL BY THE BIDDER.**