



CLARIFICATION NO. 1

HAMEHOOK RD BRIDGE #17C32 REPLACEMENT

Date: August 30, 2024
To: Bidding Documents Holders
From: Cody Smith, County Engineer/Assistant Road Department Director

In response to inquiries made by Bidding Documents holders, Deschutes County Road Department (Agency) is providing the following clarification for the above-referenced Project:

Question 1: *Can the sand cement grout mix for the piling be substituted with an ODOT 4000 PSI drilled shaft mix?*

Agency Response: The Agency may accept substitutions for the Sand/Cement Grout Mixture, provided that the minimum compressive strength of the material meets or exceeds that specified in Special Provision 00520.10(a).

Question 2: *Bid Item 034 Midwest Guardrail System, Type 3 is nested guardrail with post spacing @ 3' 1 1/2" RD482. Typically this guardrail is Midwest Guardrail Type 2A (31" height) RD407.*

Agency Response: The Agency's intent is to utilize a Type 3 (double-thickness W-beam) guardrail with a post spacing of 6'-3" as shown on Plan Sheet C5.0.